

PE CLEANER WIPES

CLEANING WIPES FOR PE, PP, PVDF AND PB



TECHNICAL SPECIFICATIONS

Base: Wipes impregnated with isopropyl alcohol

Colour: White

Flash point: K1 (<21°C)

SHELF LIFE

At least 24 months, if stored in a well-sealed packaging in a dry place at a temperature between +5°C and +25°C. Limited shelf life after opening.

PRODUCT DESCRIPTION

Cleaning wipes for PE, PP, PVDF and PB

FIELD OF APPLICATION

for cleaning and degreasing PE, PP, PVDF and PB pipes, sockets and fittings before welding.

APPLICATION

Coverage: 100 connections

Directions for use:

1. Remove the foil and pull the first wipe through the opening,
2. Dry surfaces with a clean, dry cloth.
3. Clean and degrease surfaces. Wipe is suitable for single use. Do not use dried out Wipes.
4. Remove condensation with a clean cloth and let surfaces dry thoroughly. Close packaging carefully immediately after use.

TECHNICAL PROPERTIES

Moisture resistance: Very good